

Planning Commission Study Session

TO: PLANNING COMMISSION

FROM: AMY TEMES, SENIOR PLANNER

(480) 503-6729, AMY.TEMES@GILBERTAZ.GOV

THROUGH: CATHERINE LORBEER AICP, PRINCIPAL PLANNER

(480) 503-6016, CATHERINE.LORBEER@GILBERTAZ.GOV

MEETING DATE: MAY 7, 2014

SUBJECT: A. GP14-06 PARCELS 10 & 17 OF COOLEY STATION: REQUEST FOR

MINOR GENERAL PLAN AMENDMENT TO CHANGE THE LAND USE CLASSIFICATION OF APPROXIMATELY 115 ACRES OF REAL PROPERTY GENERALLY LOCATED SOUTHEAST OF THE SOUTHEAST CORNER OF RECKER AND WILLIAMS FIELD ROADS FROM 8.47 ACRES OF RESIDENTIAL > 8 - 14 DU/ACRES AND 106.27 ACRES OF RESIDENTIAL > 5 - 8 DU/ACRES LAND USE CLASSIFICATION TO 112.7 ACRES OF RESIDENTIAL > 3.5 -

5 DU/ACRES AND 2.04 ACRES OF NEIGHBORHOOD COMMERCIAL LAND USE CLASSIFICATION; AND

B. Z14-11 PARCELS 10 & 17 OF COOLEY STATION: REQUEST TO REZONE APPROXIMATELY 115 ACRES OF REAL PROPERTY GENERALLY LOCATED SOUTHEAST OF THE SOUTHEAST CORNER OF RECKER AND WILLIAMS FIELD ROADS FROM 115 ACRES OF SINGLE FAMILY – DETACHED (SF-D) ZONING DISTRICT TO 112.7 ACRES OF SINGLE FAMILY DETACHED (SF-D) ZONING DISTRICT WITH A PLANNED AREA DEVELOPMENT (PAD) OVERLAY AND 2.04 ACRES OF NEIGHBORHOOD

COMMERCIAL (NC) WITH A PLANNED AREA DEVELOPMENT

(PAD) OVERLAY.

C. S14-05 PARCELS 10 & 17 OF COOLEY STATION: REQUEST TO APPROVE THE PRELIMINARY PLAT FOR PARCELS 10 & 17 OF

COOLEY STATION, A 416 LOT SINGLE FAMILY HOME SUBDIVISION ON APPROXIMATELY 112.7 ACRES OF REAL PROPERTY LOCATED SOUTHEAST OF THE SOUTHEAST CORNER OF RECKER AND WILLIAMS FIELD ROADS ZONED PENDING APPROVAL SINGLE FAMILY – DETACHED (SF-D) ZONING DISTRICT WITH A PLANNED AREA DEVELOPMENT (PAD) OVERLAY.

STRATEGIC INITIATIVE: Community Livability

To allow for new housing product and diversity within Cooley Station.

RECOMMENDED MOTION

A. NO MOTION REQUESTED; AND

B. NO MOTION REQUESTED; AND

C. NO MOTION REQUESTED

APPLICANT/OWNER

Company: Burch & Cracchiolo, P.A. Company: Cooley Black Canyon LLC, et al.

Name: Brennan Ray Name: Norm Nicholls Address: 702 E. Osborn Rd, #100 Address: 9140 S. Kyrene Rd

Phoenix, AZ 85014 Tempe, AZ 85284

Phone: 602-234-8794 Phone: 480-753-6789

Email: bray@bcattorneys.com Email: nnicholls@fultonhomes.com

BACKGROUND/DISCUSSION

History

Date	Description
December 19, 2006	Town Council adopted Annexation No. A05-03, Ordinance No. 1878.
March 6, 2007	The Town Council adopted Ordinance No. 1900 in case Z06-74 to rezone approximately 302 acres for the Cooley Station PAD.
June 24, 2008	The Town Council adopted Ordinance No. 2179 in case Z07-117 approving an amendment to approximately 300 acres in the Cooley Station PAD to revise several conditions of Ordinance No. 1900 in zoning case Z06-74, modifying development standards for building and landscape setbacks, and revising the street exhibits.
August 5, 2008	The Town Council approved Ordinance No. 2195 in case Z07-99, rezoning approximately 198 acres from Maricopa County to Single Family Detached (SF-D) and 41 acres of Public Facilities/ Institutional (PF/I) creating the Cooley Station Residential-2 PAD.

October 7, 2010	The Town Council adopted Ordinance No. 2304 amending		
	approximately 97 acres of the Cooley Station PAD adding exhibits and		
	development standards for Parcel 11 (Heritage at Cooley Station).		
January 17, 2013	Town Council approved Resolution No. 3148 for GP12-07 and		
	Ordinance No. 2413 for Z12-20 to rezone Parcel 16 of Cooley Station		
	for a charter school subject to the conditions.		
May 2, 2013	The Town Council adopted Ordinance No. 2525 in rezoning case Z12-		
	26 and rezoned approximately 35 acres for a single family detached and		
	Multi-Family Medium (MF-M) development in the Cooley Station		
	(Parcels 12 and 13) for Fincher Fields residential development.		
September 5, 2013	The Town Council adopted Ordinance No. 2443 in rezoning case Z13-		
	16 amending the development plan and the development standards for		
	Parcel 15 (Fulton Homes).		
November 21, 2013	The Town Council approved a technical correction to Ordinance No.		
	2443 for rezoning case Z13-16.		
February 5, 2014	Town Council adopted Ordinance No. 2473 and approved Z13-32,		
	Ashley Ward in Cooley Station on Parcel 1A.		
April 17, 2014	Town Council adopted Ordinance 2485, case Z13-37, the Bungalows at		
	Cooley Station creating a new parcel, 1B, in the Cooley Station PAD		
	and adding a street section detail for residential alleys for 24 acres.		

Overview

Cooley Station is a 775-acre master planned community with a mixed use village center that enjoys scenic views of the surrounding mountains, close proximity to ASU East, Phoenix Mesa Gateway Airport, the Santan Mall and the Loop 202. Cooley Station is planned to contain approximately 5,800 units with an overall average density of 7.5 DU / Acre. The project has been planned as a neo-traditional community; a place to live, work, and play for all socio and economic segments of the population.

The primary design characteristics of a neo traditional neighborhood development include: traditional village/neighborhood design concepts focusing on pedestrian-centered neighborhoods with primary social and economic facilities within a five-minute walk, a mixture of land uses adjacent to and within neighborhoods, centrally located parks/squares, street oriented homes with porches, stoops and courtyards, alley loaded garages or detached garages, accessory structures, in-law quarters, home offices, pedestrian/ bicycle/ transit-oriented design, and integrated residential, commercial, employment, schools, places of worship, and parks with rail and bus transit, bikeways, and pedestrian paths.

Cooley Station is a significant PAD within the Town of Gilbert and will have long term, annual economic and fiscal benefits. As Cooley Station has developed, it has become apparent to the developer that the project is missing a housing component that will allow the residents of the community to transition between neighborhoods/housing products as their lifestyles change through the years. Development of townhomes, multi-family, patio homes and zero lot products continues, but the option for a traditional single family, medium density neighborhood is missing. A traditional neighborhood, designed in the neo traditional style, can have similar residential population (larger families, mixed generational living and secondary dwelling units)

as the smaller lot alternative land uses currently designated for the project site and under construction north of Williams Field Road.

It is not the objective of the developer to drastically decrease the General Plan density for Cooley Station. The goal is to provide a stronger, more diversified residential base within the PAD community. By allowing for residential product diversity within Cooley Station, the build-out will occur sooner with less competition between the products currently under construction. The applicant/developer is requesting a Minor General Plan amendment, rezoning and preliminary plat for 115 acres of land located in the southeast corner of Cooley Station, south of the village center to accommodate a neo traditional neighborhood.

Surrounding Land Use & Zoning Designations:

	Existing Land Use Classification	Existing Zoning
North	General Office and Shopping Center	General Office and Shopping Center
South	Utility/Transportation Corridor	Public Facility/Institutional
East	Utility/Transportation Corridor	Public Facility/Institutional
West	Public Facility/Institutional	Public Facility/Institutional
Site	Residential > 5 – 8 Du/Acres	Single Family - Detached

General Plan

The General Plan amendment requests to change 8.47 acres of Residential > 8 - 14 DU/Acre and 106.27 acres of Residential > 5 - 8 Du/Acre land use classification to 112.7 acres of Residential > 3.5 - 5 Du/Acres and 2.04 acres of Neighborhood Commercial land use classification. A majority of the reduction in density constitutes one land use classification lower than what is currently approved. The reduction in density equals approximately 146.5 units.

Rezoning/Preliminary Plat

For the greater part of the project, the base zoning district of Single Family – Detached (SF – D) for 112.7 acres is not changing. Only 2.41 acres is changing to neighborhood commercial to accommodate a school expansion. If the school expansion does not occur, then it is planned that the 2 acres will be developed as a daycare facility.

Three lot sizes are proposed: 6,000 sf, 7,680 sf and 9,450 sf. The lots sizes are interspersed throughout the neighborhood creating a diverse streetscape with some of the product alley loaded and some front loaded. In no case are front loaded lots on both sides of the street, ensuring a true pedestrian friendly environment with porches, balconies, stoops and courtyards. The alley loaded product will have standard driveways and oversized alleys that allow for weekly trash and monthly over-size pick-up. The open space is centrally located with community amenities that draw people and promote interaction. The parks connect to the wide streetscape leading to the village center to the north or the local school to the southwest.

Fulton Homes is requesting the Cooley Station PAD be modified to add development standards for the new Development Plan and the Preliminary Plat reflecting the neo traditional neighborhood design. The development standards modifications provide for the neighborhood design flexibility while assuring future residents of set standards to secure the neighborhoods long term viability. The development modifications are listed below in **Bold**:

Site Development	LDC SF - D		Proposed SF – D PAD	
Minimum Lot Size	3,000	6,000	7,680	9,450
Minimum Lot Dimensions	N/A	50 ft x 120 ft	60' x 128'	70' x 135'
Min Front Yard Setback	10 ft	10 ft	12 ft	15 ft
Minimum Side Yard Setback	0 ft or 5 ft	5' and 5'	5' and 10'	5' and 10'
Minimum Rear Yard Setback	10 ft	5 ft	20 ft	25 ft
Maximum Height	36 ft / 3 story	30 ft / 2 story	30 ft / 2 story	30 ft / 2 story
Maximum Lot Coverage	60% - 1 story	60% - 1 story	60% - 1 story	60% - 1 story
	50% - 2 story	50% - 2 story	50% - 2 story	50% - 2 story

^{**} Homes adjacent to MF/L, MF/M and all non-residential categories shall not be limited to 1 story in height.

PUBLIC NOTIFICATION AND INPUT

A neighborhood meeting was held on April 23, 2014. No one from the public attended.

PROPOSITION 207

An agreement to "Waive Claims for Diminution in Value" Pursuant to A.R.S. § 12-1134 was signed by the landowners of the subject site, in conformance with Section 5.201 of the Town of Gilbert Land Development Code. This waiver is located in the case file.

STAFF REQUEST

Staff requests Planning Commission input.

Respectfully submitted,

Amy Temes Senior Planner

Attachments:

Attachment 1 Vicinity Map Attachment 2 Aerial Photo


Attachment 3 General Plan Exhibit
Attachment 4 Zoning Exhibits
Attachment 5: Development Plan


Attachment 6: Preliminary Plat/Open Space

GP14-06 / Z14-11 Attachment 1: Vicinity Map May 7, 2014


GP14-06 / Z14-11


Vicinity Map





GENERAL PLAN EXHIBIT COOLEY STATION RESIDENTIAL, OFFICE AND SHOPPING CENTER AND RESIDENTIAL 2 PADs PARCELS 10 & 17





PROJECT TEAM

LANDOWNER: POCO RANCH, INC. 17407 E. RAY ROAD HIGLEY, AZ 85236 TEL: (480)-988-3059 CONTACT: JEFF COOLEY

DEVELOPER (PARCELS 10 & 17): FULTON HOMES 9140 S. KYRENE ROAD, SUITE 202 TEMPE, AZ 85284 TEL: (480)-753-6789 FAX: (480)-753-5554 CONTACT: NORM NICHOLLS

CONSULTANT: EPS GROUP, INC. 2045 S. VINEYARD, SUITE 101 MESA, AZ 85210 TEL: (480)-503-2250 FAX: (480)-503-2258 CONTACT: JOSH HANNON

LAND USE ATTORNEY: BURCH & CRACCHIOLO 702 E. OSBORN ROAD, SUITE 200 PHOENIX, AZ 85014 TEL: (602)-234-8794 FAX: (602)-850-9794 CONTACT: BRENNAN RAY

PROJECT DATA

LEGEND

Case #

PARCEL	EXISTING GENERAL PLAN	PROPOSED GENERAL PLAN	<u>AREA</u>
10	RES. > 8-14 DU/AC	RES. > 3.5-5 DU/AC	8.47 AC. (7%)
17	RES. > 5-8 DU/AC	RES. > 3.5-5 DU/AC	104.23 AC. (91%)
17A	RES. > 5-8 DU/AC	NC	2.04 AC. (2%)
TOTAL:	-	•	114.7 AC. (100%)

PAD DEVELOPMENT BOUNDARY PARCEL BOUNDARY

PARCEL BOUNDARY CHANGE

TOWN OF GILBERT CASE NO.

Planning Commission Meeting

Town Council Meeting:

PADs 7 RES. 8 SC δo ó RES. **STATION**

GENERAL

group, Inc.

N F

ep

COOLEY


rawn by: STAFF

Not For

13-262

GPA Sheet No.

ZONING EXHIBIT COOLEY STATION RESIDENTIAL, OFFICE AND SHOPPING CENTER AND RESIDENTIAL 2 PADs PARCELS 10 & 17





E. RAY ROAD PROJECT AREA-

PROJECT TEAM

LANDOWNER:
POCO RANCH, INC.
17407 E. RAY ROAD
HIGLEY, AZ 85236
TEL: (480)-988-3059
CONTACT: JEFF COOLEY

DEVELOPER (PARCELS 10 & 17): FULTON HOMES 9140 S. KYRENE ROAD, SUITE 202 TEMPE, AZ 85284 TEL: (480)-753-6789 FAX: (480)-753-5554 CONTACT: NORM NICHOLLS

CONSULTANT: EPS GROUP, INC. 2045 S. VINEYARD, SUITE 101 MESA, AZ 85210 TEL: (480)-503-2250 FAX: (480)-503-2258 CONTACT: JOSH HANNON

LAND USE ATTORNEY: BURCH & CRACCHIOLO 702 E. OSBORN ROAD, SUITE 200 PHOENIX, AZ 85014 TEL: (602)-234-8794 FAX: (602)-850-9794 CONTACT: BRENNAN RAY

PROJECT DATA RELATED ORDINANCE NOS.

ORD. NOS. 1900, 2179, 2195, 2304 AS AMENDED BY ORD NO. 2413 541.94 TOTAL GROSS AREA: GROSS AREA (AC.) 5.86 AC. 23.78 AC 17.42 AC 8.47 AC 80.90 AC 26.88 AC 24.89 AC 25.15 AC 25.08 AC 10.00 AC 7.82 AC 5.83 AC 20.37 AC

- THIS PLAN IS NOT A CONSTRUCTION DOCUMENT. PARCEL AREAS ARE APPROXIMATE. FINAL PARCEL AREAS
- PARCEL AREAS ARE APPROXIMATE. FINAL PARCEL AREAS SHALL BE PER DEVELOPMENT APPLICATION PLANS FOR EACH PARCEL.
 THIS PROJECT SHALL BE DEVELOPED IN CONFORMANCE WITH THE TOWNS ZONING REQUIREMENTS FOR THE MULTI-FAMILYMEDIUM (MFM), MULTI-FAMILYLOW (MF/L), SINGLE FAMILY. O ETACHED (SF-D), GENERAL OFFICE (GO) AND SHOPPING CENTER (SC) ZONING DISTRICTS AND ALL DEVELOPMENT SHALL COMPLY WITH THE TOWN OF GILBERT LAND DEVELOPMENT CODE EXCEPT AS MODIFIED BY THIS ADDITED ADMINISTRA

LEGEND



PARCEL BOUNDARY CHANGE

2.04 AC

541.94 AC.

TOWN OF GILBERT CASE NO.

Case # Planning Commission Meeting: Town Council Meeting:

7 RE ॐ EXHIBIT Š Ø ó DNING RES. STATION

group, Inc.

1

ADs

Ö

OLEY



esigner: STAFF rawn by: STAFF

Not For Construction Recording


13-262

ZONING Sheet No.

GP14-06 / Z14-11 **Attachment 5: Development Plan** May 7, 2014

DEVELOPMENT PLAN

COOLEY STATION RESIDENTIAL, OFFICE AND SHOPPING CENTER AND RESIDENTIAL 2 PADs PARCELS 10 & 17



VICINITY MAP

| E. RAY ROAD PROJECT AREA-

PROJECT TEAM

17407 E. RAY ROAD HIGLEY, AZ 85236 TEL: (480)-988-3059 CONTACT: JEFF COOLEY

FULTON HOMES 9140 S. KYRENE ROAD, SUITE 202 TEMPE, AZ 85284 TEL: (480)-753-6789 FAX: (480)-753-5554 CONTACT: NORM NICHOLLS

CONSULTANT: EPS GROUP, INC. 2045 S. VINEYARD, SUITE 101 MESA, AZ 85210 TEL: (480)-503-2250 FAX: (480)-503-2258 CONTACT: JOSH HANNON

LAND USE ATTORNEY: BURCH & CRACCHIOLO 702 E. OSBORN ROAD, SUITE 200 PHOENIX, AZ 85014 TEL: (602)-234-8794 FAX: (602)-850-9794 CONTACT: BRENNAN RAY

DEVELOPER (PARCELS 10 & 17): FULTON HOMES

PROJECT DATA

ORD. NOS. 1900, 2179, 2195, 2304 AS AMENDED BY ORD NO. 2413 541.94 RELATED ORDINANCE NOS. TOTAL GROSS AREA: GROSS AREA (AC.) 5.86 AC. 23.78 AC 17.42 AC 8.47 AC 80.90 AC 26.88 AC 79.32 AC

24.89 AC 25.15 AC 25.08 AC 10.00 AC 7.82 AC 5.83 AC. 20.37 AC 2.04 AC 12.86 AC. 30.31 AC. 10.82 AC. 53.99 AC.

- THIS PLAN IS NOT A CONSTRUCTION DOCUMENT. PARCEL AREAS ARE APPROXIMATE. FINAL PARCEL AREAS SHALL BE PER DEVELOPMENT APPLICATION PLANS FOR
- THIS PROJECT SHALL BE DEVELOPED IN CONFORMANCE WITH THIS PROJECT SHALL BE DEVELOPED IN CONFORMANCE WITH THE TOWNS ZONING REQUIREMENTS FOR THE MULTI-FAMILYMEDIUM (MFM), MULTI-FAMILYALOW (MF/L), SINGLE FAMILY - DETACHED (SF-D), GENERAL OFFICE (GO) AND SHOPPING CENTER (SC) ZONING DISTRICTS AND ALL DEVELOPMENT SHALL COMPLY WITH THE TOWN OF GILBERT LAND DEVELOPMENT CODE EXCEPT AS MODIFIED BY THIS ADOPTED ORDINANCE.



Planning Commission Meeting: Town Council Meeting:

ZONING BOUNDARY

PARCEL BOUNDARY CHANGE

541.94 AC

TOWN OF GILBERT CASE NO.

CONCEPT Sheet No.


group, Inc.

PADs

Æ 8 Ø **OPMENT** ó

7

RE EVEL STATION OLEY Ö






rawn by: STAFF


Not For Recording

13-262



EXISTING & FUTURE SINGLE FAMILY TRACT


STREET SECTIONS COOLEY STATION RESIDENTIAL, OFFICE AND SHOPPING CENTER AND RESIDENTIAL 2 PADs PARCELS 10 & 17




SECTION GG - RESIDENTIAL COLLECTOR STREET - GALVESTON STREET

* NO PARKING BOTH SIDES OF STREET SIGNED PER TOG DETAIL 63.

NOTE: SETBACKS SHALL BE MEASURED FROM PROPERTY LINE (P/L). NO BUILDING OR STRUCTURE SHALL ENCROACH INTO AN EASEMENT OR TRACT.



SECTION CC - WILLIAMS FIELD ROAD - MINOR ARTERIAL STREET




SECTION AA - RECKER ROAD - MINOR ARTERIAL STREET CROSS-SECTION (IMPROVEMENTS PER TOG C.I.P. PROJECT ST-095)

NOTE: SETBACKS SHALL BE MEASURED FROM PROPERTY LINE (P/L). NO BUILDING OR STRUCTURE SHALL ENCROACH INTO AN EASEMENT OR TRACT.

SECTION GG - SF - FULL - COLLECTOR STREET SINGLE FAMILY FULL - VEST AVE


* NO PARKING BOTH SIDES OF STREET SIGNED PER TOG DETAIL 63. NOTE: SETBACKS SHALL BE MEASURED FROM PROPERTY LINE (P/L). NO BUILDING OR STRUCTURE SHALL ENCROACH INTO AN EASEMENT OR TRACT.



SECTION GG - MF - COLLECTOR STREET MULTI-FAMILY - WADE DRIVE

* NO PARKING BOTH SIDES OF STREET SIGNED PER TOG DETAIL 63

NOTE: SETBACKS SHALL BE MEASURED FROM PROPERTY LINE (P/L). NO BUILDING OR STRUCTURE SHALL ENCROACH INTO AN EASEMENT OR TRACT.



SECTION DD - BOULEVARD COLLECTOR STREET WITH MEDIAN - SUMMERTON STREET

* NO PARKING BOTH SIDES OF STREET SIGNED PER, TOG DETAIL 63

NOTE: MEDIAN TREES SHALL BE MAINTAINED TO PROVIDE A 15' VERTICAL CLEARANCE BETWEEN THE CANOPY AND THE ROADWAY PER TOG FIRE DEPT

TOWN OF GILBERT CASE NO.

Planning Commission Meeting

Town Council Meeting:

group, Inc. ™ II **Q**

> $\mathbf{D}_{\mathbf{S}}$ 7 R 8 SC

NOIL Ø 0 SE STREI

Æ ATION S OLEY

Ö



Designer: STAFF rawn by: STAFF

> Not For Constructio Recording


13-262

SECTIONS Sheet No.

STREET ALLEY - PARCELS 1B, 10 & 17

NO PARKING BOTH SIDES OF STREET SIGNED PER TOG DETAIL 63.

NOTE: SETBACKS SHALL BE MEASURED FROM ALLEY CENTERLINE. NO
BUILDING OR STRUCTURE SHALL ENCROACH INTO AN EASEMENT OR TRACT.



LYON'S GATE SINGLE FAMILY _ NOT PART OF PU & SW ESMT. R/W @ B/C LANDSCAPE TRACT

STREET SECTIONS COOLEY STATION RESIDENTIAL, OFFICE AND SHOPPING CENTER AND RESIDENTIAL 2 PADs PARCELS 10 & 17


SECTION GG - SF - COLLECTOR STREET SINGLE FAMILY - WADE DRIVE

NO PARKING BOTH SIDES OF STREET SIGNED PER TOG DETAIL 63.

NOTE: SETBACKS SHALL BE MEASURED FROM PROPERTY LINE (P/L). NO BUILDING OR STRUCTURE SHALL ENCROACH INTO AN EASEMENT OR TRACT.

STREET ALLEY - PARCEL 15


NO PARKING BOTH SIDES OF STREET SIGNED PER TOG DETAIL 63 NOTE: SETBACKS SHALL BE MEASURED FROM PROPERTY LINE (P/L). NO BUILDING OR STRUCTURE SHALL ENCROACH INTO AN EASEMENT OR TR



OCAL RESIDENTIAL STREET - PARCELS 12 & 16


NOTE: PARKING ALLOWED ON BOTH SIDES OF ROADWAY.
* MULTI USE EASEMENT DEDICATED TO TOWN OF GILBERT FOR SIDEWALKS, STREET LIGHTS, STREET UTILITIES. HOMEOWNERS ASSOCIATION TO MAINTAIN LANDS

PARCEL 12: ATTACHED 4: SIDEWALK AT BACK OF CURB ON BOTH SIDES OF STREET.
PARCELS 16 & 17: DETACHED 4: SIDEWALK WITH 4.5' PARKWAY BETWEEN SIDEWALK & BACK OF CURB
ON BOTH SIDES OF STREET.




LOCAL RESIDENTIAL STREET - PARCELS 10, 15 & 17

NOTE: PARKING ALLOWED ON BOTH SIDES OF ROADWAY



LOCAL RESIDENTIAL STREET - PARCEL 1B



N.T.S.


NOTE: COOLEY LOOP SECTION EE SHALL APPLY TO PARCEL FRONTAGE BASED ON PROPERTY ZONING DESIGNATION FOR EACH PARCEL FRONTING COOLEY LOOP. SETBACKS SHALL BE MEASURED FROM PROPERTY LINE (P/L). NO BUILDING OR STRUCTURE SHALL ENCROACH INTO AN EASEMENT OR TRACT.

SIDEWALK, AMENITY, LANDSCAPE AND PUBLIC UTILITY LANDSCAPE AND PUBLIC UTILITY EASEMEN[®] EASEMENT TRAVEL LANE TRAVEL FC TO BC LANE FC TO BC 2.0% 2.0% 6' S/W PER 6' S/W PER

MULTI FAMILY GENERAL OFFICE

SECTION EE - COOLEY LOOP - MULTI FAMILY / GENERAL OFFICE

NOTE: COOLEY LOOP SECTION FE SHALL APPLY TO PARCEL FRONTAGE BASED ON PROPERTY ZONING DESIGNATION FOR EACH PARCEL FRONTING COOLEY LOOP. SETBACKS SHALL BE MEASURED FROM PROPERTY LINE (P/L). NO BUILDING OR STRUCTURE SHALL ENCROACH INTO AN EASEMENT OR TRACT.



* NO PARKING BOTH SIDES OF STREET SIGNED PER TOG DETAIL 63

4' SIDEWALK PER MAG 230

(TYP BOTH SIDES)

SAME PAVEMENT

* PARKING BOTH SIDES OF STREET PER FIRE LANE COMPLIANCE DETAIL PEGI

TOWN OF GILBERT CASE NO.

SIDEWALK AND LANDSCAPE TRACT

L/S S/W L/S

PU & SW ES

Planning Commission Meeting: Town Council Meeting:

LANDSCAPE, SIDEWALK &

6" VERTICAL CURB AND GUTTER

PER MAG 220 TYPE 'A' W/ DEPRESSED LIP (TYP)

LANE /T

SECTION BB - RESIDENTIAL COLLECTOR STREET CROSS SECTION "B"

NOTE: SETBACKS SHALL BE MEASURED FROM PROPERTY LINE (P/L). NO BUILDING OR STRUCTURE SHALL ENCROACH INTO AN EASEMENT OR TRACT.

EXISTING & FUTURE

NOT PART OF THIS ZONING

SECTION GG - RESIDENTIAL COLLECTOR STREET - GALVESTON STREET

NOTE: SETBACKS SHALL BE MEASURED FROM PROPERTY LINE (P/L). NO BUILDING OR STRUCTURE SHALL ENCROACH INTO AN EASEMENT OR TRACT.

GALVESTON ROAD SINGLE FAMILY

. Vineyard, Ste. 101, Mesa, Arizon (480) 503-2250 **group, Inc.** S E **Q** Φ.

Ds

7

R 8 SC NOIL Ø O SE

Æ STREI ATION

S OLEY Ö



Designer: STAFF

rawn by: STAFF

Not For Construction Recording

13-262 **SECTIONS**

Sheet No. 5 of 6

OPEN SPACE & CIRCULATION PLAN VICINITY MAP | E. RAY ROAD group, Inc COOLEY STATION RESIDENTIAL, OFFICE AND SHOPPING CENTER AND RESIDENTIAL 2 PADs PARCELS 10 & 17 PROJECT AREAep SF-D LYONS GATE **PADs** PROJECT TEAM 7 DEVELOPER (PARCELS 10 & 17): FULTON HOMES FULTON HOMES 9140 S. KYRENE ROAD, SUITE 202 TEMPE, AZ 85284 TEL: (480)-753-6789 FAX: (480)-753-5554 CONTACT: NORM NICHOLLS RES. 17407 E. RAY ROAD HIGLEY, AZ 85236 TEL: (480)-988-3059 CONTACT: JEFF COOLEY 8 LAND USE ATTORNEY: BURCH & CRACCHIOLO 702 E. OSBORN ROAD, SUITE 200 PHOENIX, AZ 85014 CONSULTANT: EPS GROUP, INC. 2045 S. VINEYARD, SUITE 101 MESA, AZ 85210 8 MARICOPA AG ó TEL: (480)-503-2250 FAX: (480)-503-2258 TEL: (602)-234-8794 FAX: (602)-850-9794 CONTACT: BRENNAN RAY RES. **LEGEND** STATION F. WILLIAMS FIELD ROA PARCEL BOUNDARY CHANGE CONCEPTUAL OPEN SPACE COOLEY PARCEL 17A Designer: STAFF rawn by: STAFF Not For GP14-06 / Z14-11 **Attachment 6: Preliminary Plat/Open Space** Recording May 7, 2014 13-262 OPEN SPACE TOWN OF GILBERT CASE NO.

Sheet No. 6 of 6

Planning Commission Meeting: Town Council Meeting:

AND CIRCULATION PLAN

OPEN SPACE

PRELIMINARY PLAT

Fulton Homes at Cooley Station II A PORTION OF SECTION 36, TOWNSHIP I SOUTH, RANGE 6 EAST OF THE GILA & SALT RIVER BASE &

N 1/4 COR., SEC 36

N 89°26'55" E

MERIDIAN, MARICOPA COUNTY, ARIZONA


R: 1099.00' L: 2292.42' D: 119°30'51"

BASIS OF BEARING

26' PRIVATE VALLEY GUTTER RIBBON CURB (TYP.)



NO PARKING BOTH SIDES OF STREET SIGNED PER TOG DETAIL 63. NOTE: SETBACKS SHALL BE MEASURED FROM B/C. NO BUILDING OR STRUCTURE SHALL ENCROACH INTO AN EASEMENT OR TRACT.




LOCAL RESIDENTIAL STREET - PARCEL 15

NOTE:


*PARKING ALLOWED ON BOTH SIDES OF ROADWAY.

*SIDEWALKS ADJACENT TO OPEN SPACE TRACTS WILL BE ATTACHED.



LOCAL ENTRY RESIDENTIAL STREET - PARCEL 10 & 17

N.1.3.
NO PARKING BOTH SIDES OF STREET SIGNED PER. TOG DETAIL 63.
NOTE: MEDIAN TREES SHALL BE MAINTAINED TO PROVIDE A 15' VERTICAL
CLEARANCE BETWEEN THE CANOPY AND THE ROADWAY PER TOG FIRE DEPT




SECTION DD - BOULEVARD COLLECTOR STREET WITH MEDIAN - SUMMERTON STREET

* NO PARKING BOTH SIDES OF STREET SIGNED PER, TOG DETAIL 63. NOTE: MEDIAN TREES SHALL BE MAINTAINED TO PROVIDE A 15' VERTICAL CLEARANCE BETWEEN THE CANOPY AND THE ROADWAY PER TOG FIRE DEPT



VICINITY MAP



PROJECT TEAM

NE COR., SEC. 36

DEVELOPER: FULTON HOMES 9140 S. KYRENE, SUITE 202 TEMPE, AZ 85284 TEL: (480)-753-6789 CONTACT: NORM NICHOLLS CONSULTANT: CONSULTANT:
EPS GROUP, INC.
2045 S. VINEYARD, SUITE 101
MESA, AZ 85210
TEL: (480)-503-2250
FAX: (480)-503-2258
CONTACT: JOSH HANNON

304-49-011H: 020L: 012D: 021A:

PROJECT DATA

ASSESSOR PARCEL NO.

EXISTING GENERAL PLAN:

EXISTING ZONING: CURRENT LAND USE: GROSS AREA: NET AREA: NO. OF LOTS: GROSS DENSITY

+/- 107.32 ACRES 416 3.69 DU/AC.

3.87 DU/AC. 25.12 ACRES (22.3% OF GROSS)

GENERAL NOTES

NORTH LINE OF THE NORTHWEST QUARTER OF SECTIONS 36, T.1 S., R.6 E. ASSUMED BEARING: N 89° 27° 02" E

BENCHMARK

BCHH AT RECKER ROAD & WILLIAMS FIELD ROAD

212	
210	50%
121	29%
85	21%
	121

SHEET INDEX

IEET I	CS01	COVER SHEET
IEET 2	PP01	PRELIMINARY PLAT
IEET 3	PP02	PRELIMINARY PLAT
EET 4	PP03	PRELIMINARY PLAT
EET 5	PP04	AREA TABLES
EET 6	UT01	UTILITY PLAN
EET 7	UT02	UTILITY PLAN
EET 8	UT03	UTILITY PLAN
EET 9	GD01	PRELIMINARY GRADING & DRAINA
IEET 10	GD02	PRELIMINARY GRADING & DRAINA
IEET II	GD03	PRELIMINARY GRADING & DRAINA

304.49-011H; 020L; 012D; 021A; 010A; 015A; 016D; 014L (PORTION OF) RESIDENTIAL > 5 - 8 DU. / AC. RESIDENTIAL > 8 - 14 DU. / AC. SINGLE FAMILY DETACHED (SF-D) VACANT, UNDEVELOPED +/- 112.70 ACRES

NET DENSITY: TRACT OPEN SPACE:

THIS PLAN IS NOT A CONSTRUCTION DOCUMENT.
 LOT DIMENSIONS ARE APPROXIMATE, FINAL LOT DIMENSIONS SHALL BE PER THE FINAL PLAT.
 THE SITE IS CURRENTLY UNDER AGRICULTURAL USE. THERE ARE NO

3. THE SITE IS CURRENTLY UNDER AGRICULTURAL USE. THERE ARE NO NATIVE CACTI PRESENT.

4. WATER VALVE AND FIRE HYDRANT LOCATIONS PER TOWN OF GILBERT LDC, PUBLIC WORKS AND ENGINEERING STANDARDS/DETAILS REQUIREMENTS.

8. ALL UTILITIES TO BE UNDERGROUND.

9. ALL ROADS WILL BE CONSTRUCTED TO TOWN OF GILBERT STANDARDS, EXCEPT MODIFIED HEREIN.

10. THIS DEVELOPMENT WILL PROVIDE FOR THE INSTALLATION OF REQUIRED STREET LIGHTS.

REQUIRED 3 REET LIGHTS.

11. THE HOMEOWNERS' ASSOCIATION (HOA) WILL BE RESPONSIBLE FOR THE MAINTENANCE OF ALL LANDSCAPE TRACTS.

12. DRAINAGE CONCEPTS ARE SHOWN ON THE PRELIMINARY GRADING AND DRAINAGE PLAN.

UTILITIES

WATER	TOWN OF GILBERT
SEWER	TOWN OF GILBERT
GAS	SOUTHWEST GAS
ELECTRIC	SALT RIVER PROJECT (SRP)
TELEPHONE	CENTURYLINK / COX COMMUNICATIO
REFUSE	TOWN OF GILBERT
CARLETY	COX CARLE

BASIS OF BEARING

LOT SUMMARY

TYPE OF LOT	NO. OF LOTS	(%)
50' x 120'	210	50%
60' x 128'	121	29%
70' x 135'	85	21%
TOTAL NO. OF LOTS	416	100%

2045 S. Vineyard Ave, Suite 101 Mesa, AZ 85210 T.480.503.2250 | F.480.503.2258 w w w e p s g r o u p i n c . c o m

Station

Sheet Cover

Cooley

Homes at







CS01 Sheet No.







